

**Works**

WorkID	WorkName	Unit	Rate 1	Rate 2	Rate 3	Market	Material	Labour	Machine	Cos
<b>CIVIL WORKS</b>										
<b>PILING</b>										
37,010	PILING 300 MM DIA	m	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
37,020	PILING 350 MM DIA	m	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
37,030	PILING 400 MM DIA	m	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
37,040	PILING 450 MM DIA	m	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
37,050	PILING 500 MM DIA	m	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
37,200	PILE CHIPPING	m	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
38,000	PILING TESTS	Nos	25,000.00	0.00	0.00	0.00	0.00	0.00	0.00	0
37,000	PILING	m	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
<b>EARTH WORKS</b>										
7,020	EARTH WORKS FILLING PLINTH USING EARTH OUTSIDE	Cu.M.	154.00	161.00	168.00	169.00	100.00	40.00	0.00	140
7,030	EARTH WORKS FILLING PLINTH USING SAND	Cu.M.	704.00	736.00	768.00	769.00	600.00	40.00	0.00	640
7,010	EARTH WORKS FILLING PLINTH USING EARTH FROM SITE	Cu.M.	44.00	46.00	48.00	49.00	0.00	40.00	0.00	40
3,040	EARTH WORKS FILLING FOUNDATION USING SAND	Cu.M.	704.00	736.00	768.00	769.00	600.00	40.00	0.00	640
3,030	EARTH WORKS FILLING FOUNDATION	Cu.M.	44.00	46.00	48.00	49.00	0.00	40.00	0.00	40
1,010	EARTH WORKS EXCAVATION HARD SOIL	Cu.M.	130.00	137.00	143.00	143.00	0.00	119.00	0.00	119
1,000	EARTH WORKS EXCAVATION ORDINARY SOIL	Cu.M.	70.00	64.00	67.00	67.00	0.00	56.00	0.00	56
8	EARTH WORKS BLASTING ROCKS	Cu.M.	280.00	293.00	306.00	306.00	0.00	255.00	0.00	255
2	EARTH WORKS SITE CLEARING	Sq.M.	2.00	2.00	2.00	2.00	0.00	2.00	0.00	2
4	EARTH WORKS SITE CLEARING LS	L.S.	5,000.00	5,000.00	5,000.00	5,000.00	0.00	0.00	0.00	0
1,020	EARTH WORKS EXCAVATION	Cu.M.	90.00	98.00	102.00	102.00	0.00	85.00	0.00	85
8,010	ANTI TERMITE TREATMENT	Sq.M.	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
<b>PCC</b>										
11,010	PCC 1:2:4	Cu.M.	2,693.00	2,815.00	2,938.00	3,233.00	1,998.00	450.00	0.00	2,448

WorkID	WorkName	Unit	Rate 1	Rate 2	Rate 3	Market	Material	Labour	Machine	Cos
21,060	PCC FLOORING 1:4:8 CuM	Cu.M.	2,137.00	2,234.00	2,332.00	2,736.00	1,493.00	450.00	0.00	1,943
21,050	PCC FLOORING 1:3:6 CuM	Cu.M.	2,363.00	2,470.00	2,578.00	2,935.00	1,698.00	450.00	0.00	2,148
21,040	PCC FLOORING 1:2:4 CuM	Cu.M.	2,713.00	2,836.00	2,959.00	3,233.00	2,016.00	450.00	0.00	2,466
21,030	PCC FLOORING 1:4:8 SqM	Sq.M.	180.00	189.00	197.00	252.00	124.00	40.00	0.00	164
21,020	PCC FLOORING 1:3:6 SqM	Sq.M.	223.00	233.00	244.00	301.00	163.00	40.00	0.00	203
21,010	PCC FLOORING 1:2:4 SqM	Sq.M.	252.00	263.00	275.00	329.00	189.00	40.00	0.00	229
11,040	PCC 1:5:10	Cu.M.	2,023.00	2,115.00	2,207.00	2,630.00	1,389.00	450.00	0.00	1,839
11,020	PCC 1:3:6	Cu.M.	2,384.00	2,492.00	2,600.00	2,935.00	1,717.00	450.00	0.00	2,167
6,020	DAMP PROOF COURSE CM 1:3	Sq.M.	94.00	98.00	102.00	102.00	63.00	22.00	0.00	85
6,010	DAMP PROOF COURSE 1:2:4	Sq.M.	98.00	102.00	107.00	110.00	49.00	40.00	0.00	89
3,020	PCC FOUNDATION 1:4:8	Cu.M.	2,158.00	2,256.00	2,354.00	2,676.00	1,512.00	450.00	0.00	1,962
3,010	PCC FOUNDATION 1:3:6	Cu.M.	2,384.00	2,492.00	2,600.00	2,873.00	1,717.00	450.00	0.00	2,167
11,030	PCC 1:4:8	Cu.M.	2,158.00	2,256.00	2,354.00	2,736.00	1,512.00	450.00	0.00	1,962
<b>RUBBLE MASONRY</b>										
5,010	RRM BASEMENT CM 1:6	Cu.M.	1,159.00	1,212.00	1,265.00	1,498.00	754.00	300.00	0.00	1,054
4,030	DRM FOUNDATION	Cu.M.	566.00	592.00	618.00	865.00	315.00	200.00	0.00	515
5,050	DRM BASEMENT	Cu.M.	566.00	592.00	618.00	865.00	315.00	200.00	0.00	515
4,020	CRM FOUNDATION CM 1:6	Cu.M.	1,324.00	1,385.00	1,445.00	1,590.00	754.00	450.00	0.00	1,204
4,010	RRM FOUNDATION CM 1:6	Cu.M.	1,159.00	1,212.00	1,265.00	1,498.00	754.00	300.00	0.00	1,054
5,020	CRM BASEMENT CM 1:6	Cu.M.	1,324.00	1,385.00	1,445.00	1,590.00	754.00	450.00	0.00	1,204
<b>RCC</b>										
13,650	RCC STEPS M20	Cu.M.	5,921.00	6,190.00	6,460.00	3,917.00	2,383.00	3,000.00	0.00	5,383
14,190	RCC STRIP FOUNDATION M25	Cu.M.	3,700.00	0.00	0.00	0.00	2,733.60	461.00	0.00	3,194
14,175	RCC FOOTINGS TRAPEZOIDAL M25	Cu.M.	3,777.00	3,949.00	4,121.00	4,000.00	2,734.00	700.00	0.00	3,434
14,155	RCC PLATE SLAB FOUNDATION M25	Cu.M.	3,700.00	0.00	0.00	0.00	2,739.36	461.00	0.00	3,200
14,100	RCC PILES M25	Cu.M.	3,718.00	3,887.00	4,056.00	0.00	2,734.00	646.00	0.00	3,380
14,000	RCC ALL RCCS M25	Cu.M.	4,113.00	4,300.00	4,487.00	4,640.00	2,739.00	1,000.00	0.00	3,739
13,801	RCC SLOPED ROOF SLABS M20	Cu.M.	4,381.00	4,580.00	4,780.00	0.00	2,383.00	1,600.00	0.00	3,983

WorkID	WorkName	Unit	Rate 1	Rate 2	Rate 3	Market	Material	Labour	Machine	Cos
13,800	RCC ROOF SLABS M20	Cu.M.	3,831.00	4,005.00	4,180.00	3,937.00	2,383.00	1,100.00	0.00	3,483
13,700	RCC LANDINGS M20	Cu.M.	3,831.00	4,005.00	4,180.00	3,937.00	2,383.00	1,100.00	0.00	3,483
14,250	RCC COLUMNS M25	Cu.M.	5,323.00	5,565.00	5,807.00	4,418.00	2,739.00	2,100.00	0.00	4,839
13,600	RCC SUN SHADES M20	Cu.M.	3,831.00	4,005.00	4,180.00	3,937.00	2,383.00	1,100.00	0.00	3,483
13,550	RCC DROP SLABS M20	Cu.M.	4,601.00	4,810.00	5,020.00	4,494.00	2,383.00	1,800.00	0.00	4,183
13,500	RCC PARAPET SLABS M20	Cu.M.	4,601.00	4,810.00	5,020.00	4,494.00	2,383.00	1,800.00	0.00	4,183
13,450	RCC SLABS M20	Cu.M.	3,831.00	4,005.00	4,180.00	3,937.00	2,383.00	1,100.00	0.00	3,483
13,400	RCC FLOOR SLABS M20	Cu.M.	3,831.00	4,005.00	4,180.00	3,937.00	2,383.00	1,100.00	0.00	3,483
13,350	RCC BEAMS M20	Cu.M.	4,601.00	4,810.00	5,020.00	4,050.00	2,383.00	1,800.00	0.00	4,183
13,750	RCC WAIST SLABS M20	Cu.M.	3,831.00	4,005.00	4,180.00	3,937.00	2,383.00	1,100.00	0.00	3,483
14,500	RCC PARAPET SLABS M25	Cu.M.	4,993.00	5,220.00	5,447.00	5,084.00	2,739.00	1,800.00	0.00	4,539
13,300	RCC LINTELS M20	Cu.M.	4,601.00	4,810.00	5,020.00	3,917.00	2,383.00	1,800.00	0.00	4,183
14,801	RCC SLOPED ROOF SLABS M25	Cu.M.	4,773.00	4,990.00	5,207.00	0.00	2,739.00	1,600.00	0.00	4,339
14,800	RCC ROOF SLABS M25	Cu.M.	4,223.00	4,415.00	4,607.00	4,528.00	2,739.00	1,100.00	0.00	3,839
14,750	RCC WAIST SLABS M25	Cu.M.	4,223.00	4,415.00	4,607.00	4,528.00	2,739.00	1,100.00	0.00	3,839
14,700	RCC LANDINGS M25	Cu.M.	4,223.00	4,415.00	4,607.00	4,528.00	2,739.00	1,100.00	0.00	3,839
14,650	RCC STEPS M25	Cu.M.	6,313.00	6,600.00	6,887.00	4,507.00	2,739.00	3,000.00	0.00	5,739
14,200	RCC BELTS M25	Cu.M.	4,883.00	5,105.00	5,327.00	4,418.00	2,739.00	1,700.00	0.00	4,439
14,550	RCC DROP SLABS M25	Cu.M.	4,993.00	5,220.00	5,447.00	5,084.00	2,739.00	1,800.00	0.00	4,539
14,210	RCC PLINTH BEAMS M25	Cu.M.	4,800.00	0.00	0.00	0.00	2,739.36	646.00	0.00	3,385
14,450	RCC SLABS M25	Cu.M.	4,223.00	4,415.00	4,607.00	4,528.00	2,739.00	1,100.00	0.00	3,839
14,400	RCC FLOOR SLABS M25	Cu.M.	4,223.00	4,415.00	4,607.00	4,528.00	2,739.00	1,100.00	0.00	3,839
14,350	RCC BEAMS M25	Cu.M.	4,993.00	5,220.00	5,447.00	4,640.00	2,739.00	1,800.00	0.00	4,539
14,300	RCC LINTELS M25	Cu.M.	4,993.00	5,220.00	5,447.00	4,507.00	2,739.00	1,800.00	0.00	4,539
14,275	RCC COLUMNS ROUND M25	Cu.M.	6,307.00	6,594.00	6,881.00	4,000.00	2,734.00	3,000.00	0.00	5,734
14,150	RCC FOOTINGS M25	Cu.M.	3,728.00	3,897.00	4,067.00	4,196.00	2,739.00	650.00	0.00	3,389
14,600	RCC SUN SHADES M25	Cu.M.	4,223.00	4,415.00	4,607.00	4,528.00	2,739.00	1,100.00	0.00	3,839
12,200	RCC BELTS M15	Cu.M.	4,088.00	4,273.00	4,459.00	3,516.00	2,016.00	1,700.00	0.00	3,716
12,550	RCC DROP SLABS M15	Cu.M.	4,198.00	4,388.00	4,579.00	4,182.00	2,016.00	1,800.00	0.00	3,816
12,500	RCC PARAPET SLABS M15	Cu.M.	4,198.00	4,388.00	4,579.00	4,182.00	2,016.00	1,800.00	0.00	3,816

WorkID	WorkName	Unit	Rate 1	Rate 2	Rate 3	Market	Material	Labour	Machine	Cos
12,450	RCC SLABS M15	Cu.M.	3,428.00	3,583.00	3,739.00	3,625.00	2,016.00	1,100.00	0.00	3,116
12,400	RCC FLOOR SLABS M15	Cu.M.	3,428.00	3,583.00	3,739.00	3,625.00	2,016.00	1,100.00	0.00	3,116
12,350	RCC BEAMS M15	Cu.M.	4,198.00	4,388.00	4,579.00	3,738.00	2,016.00	1,800.00	0.00	3,816
12,300	RCC LINTELS M15	Cu.M.	4,198.00	4,388.00	4,579.00	3,605.00	2,016.00	1,800.00	0.00	3,816
12,600	RCC SUN SHADES M15	Cu.M.	3,428.00	3,583.00	3,739.00	3,625.00	2,016.00	1,100.00	0.00	3,116
14,160	RCC PILE CAPS M25	Cu.M.	3,700.00	0.00	0.00	0.00	2,739.36	461.00	0.00	3,200
12,275	RCC COLUMNS ROUND M15	Cu.M.	5,518.00	5,768.00	6,019.00	3,200.00	2,016.00	3,000.00	0.00	5,016
12,190	RCC STRIP FOUNDATION M15	Cu.M.	3,000.00	0.00	0.00	0.00	2,016.00	461.00	0.00	2,477
12,175	RCC FOOTINGS TRAPEZOIDAL M15	Cu.M.	2,988.00	3,123.00	3,259.00	2,800.00	2,016.00	700.00	0.00	2,716
12,160	RCC PILE CAPS M15	Cu.M.	3,000.00	0.00	0.00	0.00	2,016.00	461.00	0.00	2,477
12,155	RCC PLATE SLAB FOUNDATION M15	Cu.M.	3,000.00	0.00	0.00	0.00	2,016.00	461.00	0.00	2,477
12,150	RCC FOOTINGS M15	Cu.M.	2,933.00	3,066.00	3,199.00	3,294.00	2,016.00	650.00	0.00	2,666
12,100	RCC PILES M15	Cu.M.	2,928.00	3,061.00	3,194.00	0.00	2,016.00	646.00	0.00	2,662
13,275	RCC COLUMNS ROUND M20	Cu.M.	5,921.00	6,190.00	6,460.00	3,400.00	2,383.00	3,000.00	0.00	5,383
12,250	RCC COLUMNS M15	Cu.M.	4,528.00	4,733.00	4,939.00	3,516.00	2,016.00	2,100.00	0.00	4,116
12,210	RCC PLINTH BEAMS M15	Cu.M.	4,000.00	0.00	0.00	0.00	2,016.00	831.00	0.00	2,847
13,200	RCC BELTS M20	Cu.M.	4,491.00	4,695.00	4,900.00	3,828.00	2,383.00	1,700.00	0.00	4,083
13,190	RCC STRIP FOUNDATION M20	Cu.M.	3,300.00	0.00	0.00	0.00	2,383.20	461.00	0.00	2,844
13,175	RCC FOOTINGS TRAPEZOIDAL M20	Cu.M.	3,391.00	3,545.00	3,700.00	3,000.00	2,383.00	700.00	0.00	3,083
13,160	RCC PILE CAPS M20	Cu.M.	3,300.00	0.00	0.00	0.00	2,383.20	461.00	0.00	2,844
13,155	RCC PLATE SLAB FOUNDATION M20	Cu.M.	3,300.00	0.00	0.00	0.00	2,383.20	461.00	0.00	2,844
13,150	RCC FOOTINGS M20	Cu.M.	3,336.00	3,488.00	3,640.00	3,606.00	2,383.00	650.00	0.00	3,033
12,650	RCC STEPS M15	Cu.M.	5,518.00	5,768.00	6,019.00	3,605.00	2,016.00	3,000.00	0.00	5,016
13,000	RCC ALL RCCS M20	Cu.M.	3,721.00	3,890.00	4,060.00	4,050.00	2,383.00	1,000.00	0.00	3,383
13,210	RCC PLINTH BEAMS M20	Cu.M.	4,500.00	0.00	0.00	0.00	2,383.20	646.00	0.00	3,029
12,801	RCC SLOPED ROOF SLABS M15	Cu.M.	3,978.00	4,158.00	4,339.00	0.00	2,016.00	1,600.00	0.00	3,616
12,800	RCC ROOF SLABS M15	Cu.M.	3,428.00	3,583.00	3,739.00	3,625.00	2,016.00	1,100.00	0.00	3,116
12,750	RCC WAIST SLABS M15	Cu.M.	3,428.00	3,583.00	3,739.00	3,625.00	2,016.00	1,100.00	0.00	3,116

WorkID	WorkName	Unit	Rate 1	Rate 2	Rate 3	Market	Material	Labour	Machine	Cos
12,000	RCC ALL RCCS M15	Cu.M.	3,318.00	3,468.00	3,619.00	3,738.00	2,016.00	1,000.00	0.00	3,016
12,700	RCC LANDINGS M15	Cu.M.	3,428.00	3,583.00	3,739.00	3,625.00	2,016.00	1,100.00	0.00	3,116
13,250	RCC COLUMNS M20	Cu.M.	4,931.00	5,155.00	5,380.00	3,828.00	2,383.00	2,100.00	0.00	4,483
13,100	RCC PILES M20	Cu.M.	3,332.00	3,483.00	3,635.00	0.00	2,383.00	646.00	0.00	3,029
<b>FORM WORKS</b>										
36,000	FORM WORK RCC	Sq.M.	134.00	140.00	146.00	0.00	0.00	122.00	0.00	122
<b>STEEL REQUIREMENTS</b>										
35,000	STEEL REQUIREMENT S	Kg	28.00	29.00	30.00	30.00	21.00	4.00	0.00	25
35,001	STEEL REQUIREMENT S	Kg	28.00	29.00	30.00	30.00	21.00	4.00	0.00	25
35,002	STEEL REQUIREMENT S	Kg	28.00	29.00	30.00	25.00	21.00	4.00	0.00	25
<b>STEEL WORKS</b>										
40,110	PAINTING STEEL BARS 12MM	Sq.M.	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
40,120	PAINTING STEEL BARS 16MM	Sq.M.	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
40,100	PAINTING STEEL BARS 8MM	Sq.M.	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
39,120	STEEL BARS 16MM	Kg	26.00	0.00	0.00	0.00	0.00	0.00	0.00	0
39,110	STEEL BARS 12MM	Kg	25.00	0.00	0.00	0.00	0.00	0.00	0.00	0
39,100	STEEL BARS 8MM	Kg	25.00	0.00	0.00	0.00	0.00	0.00	0.00	0
<b>BRICK WORKS</b>										
9,020	BRICK WORKS CM 1:3	Cu.M.	2,108.00	2,203.00	2,299.00	2,490.00	1,616.00	300.00	0.00	1,916
9,090	BRICK WORKS HOLLOW BRICKS CM 1:6	Cu.M.	1,419.00	1,483.00	1,548.00	1,627.00	1,040.00	250.00	0.00	1,290
9,080	BRICK WORKS INTER LOCKING	Cu.M.	1,496.00	1,564.00	1,632.00	1,723.00	960.00	400.00	0.00	1,360
9,070	BRICK WORKS LATERITE CM 1:6	Cu.M.	1,356.00	1,418.00	1,480.00	1,265.00	833.00	400.00	0.00	1,233
9,060	BRICK WORKS CM 1:8	Cu.M.	1,759.00	1,839.00	1,919.00	2,216.00	1,299.00	300.00	0.00	1,599
9,050	BRICK WORKS CM 1:6	Cu.M.	1,818.00	1,901.00	1,984.00	2,278.00	1,353.00	300.00	0.00	1,653
10,020	BRICK WORKS ARCH CM 1:4	Cu.M.	2,093.00	2,188.00	2,284.00	2,550.00	1,453.00	450.00	0.00	1,903
10,010	BRICK WORKS ARCH CM 1:3	Cu.M.	2,308.00	2,413.00	2,518.00	2,652.00	1,648.00	450.00	0.00	2,098
9,040	BRICK WORKS CM 1:5	Cu.M.	1,861.00	1,946.00	2,030.00	2,322.00	1,392.00	300.00	0.00	1,692
9,030	BRICK WORKS CM 1:4	Cu.M.	1,847.00	1,931.00	2,015.00	2,388.00	1,379.00	300.00	0.00	1,679

WorkID	WorkName	Unit	Rate 1	Rate 2	Rate 3	Market	Material	Labour	Machine	Cos
2,010	BRICK WORKS SOLING IN FOUNDATION	Cu.M.	119.00	124.00	130.00	130.00	106.00	2.00	0.00	108
4,040	BRICK WORKS FOUNDATION CM 1:3	Cu.M.	2,088.00	2,183.00	2,278.00	2,470.00	1,598.00	300.00	0.00	1,898
4,050	BRICK WORKS FOUNDATION CM 1:4	Cu.M.	1,965.00	2,054.00	2,143.00	2,408.00	1,486.00	300.00	0.00	1,786
5,030	BRICK WORKS BASEMENT CM 1:3	Cu.M.	2,088.00	2,183.00	2,278.00	2,470.00	1,598.00	300.00	0.00	1,898
5,040	BRICK WORKS BASEMENT CM 1:4	Cu.M.	1,988.00	2,078.00	2,168.00	2,778.00	1,507.00	300.00	0.00	1,807
9,010	BRICK WORKS CM 1:2	Cu.M.	2,254.00	2,356.00	2,459.00	2.00	1,749.00	300.00	0.00	2,049
<b>FLOOR AND WALL FINISHES</b>										
23,010	WALL FINISHING CUDAPPAH STONE	Sq.M.	459.00	480.00	500.00	274.00	242.00	175.00	0.00	417
24,008	SKIRTING TERRAZZO TILES IN M	m	37.00	39.00	41.00	17.00	25.00	9.00	0.00	34
24,004	SKIRTING GRANITE TILES IN M	m	168.00	176.00	184.00	41.00	135.00	18.00	0.00	153
23,012	WALL FINISHING MARBLE SLABS	Sq.M.	176.00	184.00	192.00	0.00	600.00	160.00	0.00	760
23,013	WALL FINISHING BROKEN MARBLE	Sq.M.	500.00	0.00	0.00	0.00	0.00	0.00	0.00	0
23,014	WALL FINISHING PAVEMENT TILES	m2	250.00	0.00	0.00	0.00	63.00	175.20	0.00	238
24,001	SKIRTING NONE IN M	m	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
24,002	SKIRTING MARBLE TILES IN M	m	95.00	99.00	103.00	31.00	47.00	39.00	0.00	86
24,003	SKIRTING CERAMIC TILES IN M	m	76.00	79.00	83.00	18.00	49.00	20.00	0.00	69
23,011	WALL FINISHING RED OXIDE	Sq.M.	166.00	174.00	181.00	212.00	86.00	65.00	0.00	151
24,005	SKIRTING MOSAIC FLOORING IN M	m	80.00	0.00	0.00	0.00	0.00	0.00	0.00	0
23,009	WALL FINISHING KOTAH STONE	Sq.M.	459.00	480.00	500.00	274.00	242.00	175.00	0.00	417
24,007	SKIRTING CEMENT FLOATING COAT IN M	m	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0

WorkID	WorkName	Unit	Rate 1	Rate 2	Rate 3	Market	Material	Labour	Machine	Cos
23,004	WALL FINISHING GRANITE TILES	Sq.M.	1,614.00	1,687.00	1,760.00	400.00	1,292.00	175.00	0.00	1,467
24,009	SKIRTING KOTAH STONE IN M	m	47.00	49.00	52.00	28.00	25.00	18.00	0.00	43
24,010	SKIRTING CUDAPPAH STONE IN M	m	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0
24,011	SKIRTING RED OXIDE IN M	m	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0
24,012	SKIRTING MARBLE SLABS IN M	m	44.00	46.00	48.00	0.00	0.00	40.00	0.00	40
24,013	SKIRTING BROKEN MARBLE IN M	m	60.00	0.00	0.00	0.00	0.00	0.00	0.00	0
24,014	SKIRTING PAVEMENT TILES IN M	m	40.00	0.00	0.00	0.00	35.00	175.20	0.00	210
44,003	SKIRTING CERAMIC TILES IN SqM	Sq.M.	587.00	614.00	641.00	0.00	469.00	65.00	0.00	534
24,006	SKIRTING VITRIFIED TILES IN M	m	120.00	125.00	131.00	31.00	91.00	18.00	0.00	109
22,010	FLOOR FINISHING CUDAPPAH STONE	Sq.M.	459.00	480.00	500.00	400.00	242.00	175.00	0.00	417
44,002	SKIRTING MARBLE TILES IN SqM	Sq.M.	640.00	669.00	698.00	0.00	452.00	130.00	0.00	582
22,001	FLOOR FINISHING NONE	Cu.M.	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
22,002	FLOOR FINISHING MARBLE TILES	Sq.M.	640.00	669.00	698.00	700.00	452.00	130.00	0.00	582
22,003	FLOOR FINISHING CERAMIC TILES	Sq.M.	587.00	614.00	641.00	600.00	469.00	65.00	0.00	534
22,004	FLOOR FINISHING GRANITE TILES	Sq.M.	1,614.00	1,687.00	1,760.00	1,400.00	1,292.00	175.00	0.00	1,467
22,005	FLOOR FINISHING MOSAIC FLOORING	Sq.M.	563.00	589.00	614.00	614.00	307.00	205.00	0.00	512
22,006	FLOOR FINISHING VITRIFIED TILES	Sq.M.	1,152.00	1,204.00	1,256.00	1,000.00	872.00	175.00	0.00	1,047
22,007	FLOOR FINISHING CEMENT FLOATING COAT	Sq.M.	105.00	109.00	114.00	151.00	35.00	60.00	0.00	95

WorkID	WorkName	Unit	Rate 1	Rate 2	Rate 3	Market	Material	Labour	Machine	Cos
23,006	WALL FINISHING VITRIFIED TILES	Sq.M.	1,152.00	1,204.00	1,256.00	305.00	872.00	175.00	0.00	1,047
22,009	FLOOR FINISHING KOTAH STONE	Sq.M.	459.00	480.00	500.00	500.00	242.00	175.00	0.00	417
23,008	WALL FINISHING TERRAZZO TILES	Sq.M.	674.00	705.00	736.00	498.00	438.00	175.00	0.00	613
22,011	FLOOR FINISHING RED OXIDE	Sq.M.	166.00	174.00	181.00	212.00	86.00	65.00	0.00	151
22,012	FLOOR FINISHING MARBLE SLABS	Sq.M.	176.00	184.00	192.00	0.00	662.00	160.00	0.00	822
22,013	FLOOR FINISHING BROKEN MARBLE	Sq.M.	500.00	0.00	0.00	0.00	306.80	205.00	0.00	511
22,014	FLOOR FINISHING PAVEMENT TILES	m2	250.00	0.00	0.00	0.00	63.00	175.20	0.00	238
23,001	WALL FINISHING NONE	Sq.M.	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
23,002	WALL FINISHING MARBLE TILES	Sq.M.	640.00	669.00	698.00	299.00	452.00	130.00	0.00	582
23,003	WALL FINISHING CERAMIC TILES	Sq.M.	587.00	614.00	641.00	184.00	469.00	65.00	0.00	534
23,005	WALL FINISHING MOSAIC FLOORING	Sq.M.	563.00	589.00	614.00	614.00	307.00	205.00	0.00	512
23,007	WALL FINISHING CEMENT FLOATING COAT	Sq.M.	105.00	109.00	114.00	151.00	35.00	60.00	0.00	95
22,008	FLOOR FINISHING TERRAZZO TILES	Sq.M.	488.00	511.00	533.00	295.00	269.00	175.00	0.00	444
62,010	PAVING COBBLE STONES	Sq.M.	100.00	0.00	0.00	0.00	0.00	0.00	0.00	0
44,001	SKIRTING NONE IN SqM	Sq.M.	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
44,014	SKIRTING PAVEMENT TILES IN M2	m2	250.00	0.00	0.00	0.00	63.00	175.20	0.00	238
44,013	SKIRTING BROKEN MARBLE IN SqM	Sq.M.	600.00	0.00	0.00	0.00	0.00	0.00	0.00	0
44,012	SKIRTING MARBLE SLABS IN SqM	Sq.M.	176.00	184.00	192.00	0.00	0.00	160.00	0.00	160



WorkID	WorkName	Unit	Rate 1	Rate 2	Rate 3	Market	Material	Labour	Machine	Cos
44,011	SKIRTING RED OXIDE IN SqM	Sq.M.	480.00	501.00	523.00	0.00	371.00	65.00	0.00	436
44,010	SKIRTING CUDAPPAH STONE IN SqM	Sq.M.	266.00	278.00	290.00	0.00	242.00	0.00	0.00	242
44,008	SKIRTING TERRAZZO TILES IN SqM	Sq.M.	278.00	291.00	304.00	0.00	253.00	0.00	0.00	253
44,007	SKIRTING CEMENT FLOATING COAT IN SqM	Sq.M.	105.00	109.00	114.00	0.00	35.00	60.00	0.00	95
44,006	SKIRTING VITRIFIED TILES IN M2	Sq.M.	139.00	145.00	151.00	0.00	35.00	91.00	0.00	126
44,005	SKIRTING MOSAIC FLOORING IN SqM	Sq.M.	319.00	334.00	348.00	0.00	290.00	0.00	0.00	290
44,004	SKIRTING GRANITE TILES IN SqM	Sq.M.	1,421.00	1,486.00	1,550.00	0.00	1,292.00	0.00	0.00	1,292
44,009	SKIRTING KOTAH STONE IN SqM	Sq.M.	266.00	278.00	290.00	0.00	242.00	0.00	0.00	242
<b>DOORS AND WINDOWS</b>										
50,101	DOORS WOOD	Sq.M.	2,420.00	2,530.00	2,640.00	2,780.00	1,600.00	2,200.00	0.00	3,800
20,008	SHUTTERS METAL GLAZED	Sq.M.	132.00	138.00	144.00	144.00	120.00	0.00	0.00	120
20,009	SHUTTERS ALUMINIUM GLAZED	Sq.M.	136.00	143.00	149.00	149.00	124.00	0.00	0.00	124
20,010	SHUTTERS SYNTHETIC PANELLED	Sq.M.	239.00	250.00	260.00	0.00	0.00	217.00	0.00	217
20,011	SHUTTERS CHERUTEAK PANELLED	Sq.M.	2,552.00	2,668.00	2,784.00	0.00	1,500.00	820.00	0.00	2,320
20,012	SHUTTERS CHERUTEAK GLAZED	Sq.M.	1,694.00	1,771.00	1,848.00	0.00	720.00	820.00	0.00	1,540
20,013	SHUTTERS THAMBAKOM PANELLED	Sq.M.	2,000.00	0.00	0.00	0.00	0.00	0.00	0.00	0
43,010	GRILLE FOR WINDOWS 12 KG/SqM	Sq.M.	360.00	0.00	0.00	0.00	0.00	0.00	0.00	0
51,101	WINDOWS WOOD	Sq.M.	2,420.00	2,530.00	2,640.00	2,780.00	1,120.00	2,200.00	0.00	3,320
43,030	GRILLE FOR WINDOWS 16 KG/SqM	Sq.M.	480.00	0.00	0.00	0.00	0.00	0.00	0.00	0
20,007	SHUTTERS MAHOGANY GLAZED	Sq.M.	1,650.00	1,725.00	1,800.00	1,416.00	680.00	820.00	0.00	1,500
20,004	SHUTTERS METAL ROLLING	Sq.M.	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
43,020	GRILLE FOR WINDOWS 14 KG/SqM	Sq.M.	450.00	0.00	0.00	0.00	0.00	0.00	0.00	0
19,002	FRAMES TEAK	Cu.M.	39,380.00	41,170.00	42,960.00	42,960.00	33,600.00	2,200.00	0.00	35,800

WorkID	WorkName	Unit	Rate 1	Rate 2	Rate 3	Market	Material	Labour	Machine	Cos
20,006	SHUTTERS TEAK GLAZED	Sq.M.	1,738.00	1,817.00	1,896.00	1,512.00	760.00	820.00	0.00	1,580
19,001	FRAMES WOOD	Cu.M.	25,520.00	26,680.00	27,840.00	27,840.00	21,000.00	2,200.00	0.00	23,200
20,005	SHUTTERS WOOD GLAZED	Sq.M.	1,474.00	1,541.00	1,608.00	1,224.00	520.00	820.00	0.00	1,340
19,003	FRAMES MAHOGANY	Cu.M.	34,760.00	36,340.00	37,920.00	37,920.00	29,400.00	2,200.00	0.00	31,600
19,004	FRAMES CONCRETE	Cu.M.	2,609.00	2,728.00	2,846.00	3,233.00	1,962.00	410.00	0.00	2,372
19,005	FRAMES CHERUTEAK	Cu.M.	37,070.00	38,755.00	40,440.00	0.00	31,500.00	2,200.00	0.00	33,700
19,006	FRAMES ANJILY	Cu.M.	25,520.00	26,680.00	27,840.00	0.00	21,000.00	2,200.00	0.00	23,200
20,000	SHUTTERS NONE	Sq.M.	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
20,001	SHUTTERS WOOD PANELLED	Sq.M.	2,002.00	2,093.00	2,184.00	1,800.00	1,000.00	820.00	0.00	1,820
20,002	SHUTTERS TEAK PANELLED	Sq.M.	2,662.00	2,783.00	2,904.00	2,520.00	1,600.00	820.00	0.00	2,420
20,003	SHUTTERS MAHOGANY PANELLED	Sq.M.	2,442.00	2,553.00	2,664.00	2,280.00	1,400.00	820.00	0.00	2,220
19,007	FRAMES THAMBAKOM	Cu.M.	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
19,000	FRAMES NONE	Cu.M.	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
<b>PLASTERING AND POINTING</b>										
48,040	PLASTERING WALLS INT. CM 1:5 12 MM	Sq.M.	33.00	34.00	36.00	90.00	0.00	30.00	0.00	30
17,020	PLASTERING CEILINGS AND SLABS CM 1:3	Sq.M.	72.00	75.00	78.00	78.00	25.00	40.00	0.00	65
17,030	PLASTERING CEILINGS AND SLABS CM 1:4	Sq.M.	65.00	68.00	71.00	74.00	19.00	40.00	0.00	59
17,040	PLASTERING CEILINGS AND SLABS CM 1:5	Sq.M.	65.00	68.00	71.00	74.00	0.00	40.00	0.00	40
18,010	PLASTERING ROOF TOP CM 1:2 12 MM	Sq.M.	77.00	80.00	84.00	109.00	45.00	25.00	0.00	70
18,020	PLASTERING ROOF TOP CM 1:3 12 MM	Sq.M.	67.00	70.00	73.00	101.00	36.00	25.00	0.00	61
18,030	PLASTERING ROOF TOP CM 1:4 12 MM	Sq.M.	62.00	64.00	67.00	94.00	31.00	25.00	0.00	56
18,050	PLASTERING ROOF TOP CM 1:5 12 MM	Sq.M.	62.00	64.00	67.00	94.00	0.00	25.00	0.00	25
46,050	PLASTERING WALLS EXT. CM 1:6 12 MM	Sq.M.	33.00	34.00	36.00	88.00	0.00	30.00	0.00	30
48,050	PLASTERING WALLS INT. CM 1:6 12 MM	Sq.M.	33.00	34.00	36.00	88.00	0.00	30.00	0.00	30
17,010	PLASTERING CEILINGS AND SLABS CM 1:2	Sq.M.	69.00	72.00	76.00	83.00	23.00	40.00	0.00	63

WorkID	WorkName	Unit	Rate 1	Rate 2	Rate 3	Market	Material	Labour	Machine	Cos
15,020	PLASTERING BASEMENT CM 1:3 12MM	Sq.M.	89.00	93.00	97.00	98.00	36.00	45.00	0.00	81
46,040	PLASTERING WALLS EXT. CM 1:5 12 MM	Sq.M.	33.00	34.00	36.00	90.00	0.00	30.00	0.00	30
15,050	PLASTERING BASEMENT CM 1:6 12MM	Sq.M.	77.00	80.00	84.00	86.00	25.00	45.00	0.00	70
15,010	PLASTERING BASEMENT CM 1:2 12MM	Sq.M.	100.00	105.00	109.00	109.00	45.00	46.00	0.00	91
15,040	PLASTERING BASEMENT CM 1:5 12MM	Sq.M.	79.00	83.00	86.00	90.00	27.00	45.00	0.00	72
16,070	POINTING BRICKS CM 1:3	Sq.M.	51.00	53.00	55.00	61.00	11.00	35.00	0.00	46
15,030	PLASTERING BASEMENT CM 1:4 12MM	Sq.M.	84.00	87.00	91.00	94.00	31.00	45.00	0.00	76
15,060	POINTING BRICKS BASEMENT CM 1:2	Sq.M.	53.00	55.00	58.00	66.00	13.00	35.00	0.00	48
15,070	POINTING BRICKS BASEMENT CM 1:3	Sq.M.	51.00	53.00	55.00	61.00	11.00	35.00	0.00	46
16,010	PLASTERING WALLS CM 1:2 12 MM	Sq.M.	78.00	82.00	85.00	104.00	41.00	30.00	0.00	71
16,020	PLASTERING WALLS CM 1:3 12 MM	Sq.M.	73.00	76.00	79.00	101.00	36.00	30.00	0.00	66
16,030	PLASTERING WALLS CM 1:4 12 MM	Sq.M.	67.00	70.00	73.00	94.00	31.00	30.00	0.00	61
16,040	PLASTERING WALLS CM 1:5 12 MM	Sq.M.	63.00	66.00	68.00	90.00	27.00	30.00	0.00	57
16,050	PLASTERING WALLS CM 1:6 12 MM	Sq.M.	61.00	63.00	66.00	88.00	25.00	30.00	0.00	55
16,060	POINTING BRICKS CM 1:2	Sq.M.	53.00	55.00	58.00	66.00	13.00	35.00	0.00	48
					<b>PAINTING</b>					
49,050	PAINTING WALLS INT. CEMENT PAINT	Sq.M.	20.00	21.00	22.00	35.00	11.00	18.00	0.00	29
47,030	PAINTING WALLS EXT. PLASTIC EMULSION	Sq.M.	44.00	46.00	48.00	48.00	18.00	22.00	0.00	40
29,010	PAINTING ROOFTOPS WHITE WASHING	Sq.M.	11.00	12.00	12.00	11.00	2.00	8.00	0.00	10
29,020	PAINTING ROOFTOPS DISTEMPER	Sq.M.	42.00	44.00	46.00	46.00	10.00	28.00	0.00	38

WorkID	WorkName	Unit	Rate 1	Rate 2	Rate 3	Market	Material	Labour	Machine	Cos
29,040	PAINTING ROOFTOPS WHITE CEMENT	Sq.M.	29.00	30.00	31.00	31.00	8.00	18.00	0.00	26
47,010	PAINTING WALLS EXT. WHITE WASHING	Sq.M.	11.00	12.00	12.00	11.00	2.00	8.00	0.00	10
47,020	PAINTING WALLS EXT. DISTEMPER	Sq.M.	42.00	44.00	46.00	46.00	10.00	28.00	0.00	38
29,000	PAINTING ROOFTOPS COLOUR WASHING	Sq.M.	12.00	13.00	13.00	12.00	3.00	8.00	0.00	11
47,040	PAINTING WALLS EXT. WHITE CEMENT	Sq.M.	29.00	30.00	31.00	31.00	8.00	18.00	0.00	26
47,050	PAINTING WALLS EXT. CEMENT PAINT	Sq.M.	20.00	21.00	22.00	35.00	11.00	18.00	0.00	29
47,060	PAINTING WALLS EXT. COLOUR WASHING	Sq.M.	12.00	13.00	13.00	12.00	3.00	8.00	0.00	11
49,010	PAINTING WALLS INT. WHITE WASHING	Sq.M.	11.00	12.00	12.00	11.00	2.00	8.00	0.00	10
49,020	PAINTING WALLS INT. DISTEMPER	Sq.M.	42.00	44.00	46.00	46.00	10.00	28.00	0.00	38
49,040	PAINTING WALLS INT. WHITE CEMENT	Sq.M.	29.00	30.00	31.00	31.00	8.00	18.00	0.00	26
49,060	PAINTING WALLS INT. COLOUR WASHING	Sq.M.	12.00	13.00	13.00	12.00	3.00	8.00	0.00	11
29,030	PAINTING ROOFTOPS PLASTIC EMULSION	Sq.M.	44.00	46.00	48.00	48.00	18.00	22.00	0.00	40
28,050	PAINTING CEILINGS AND SLABS COLOUR WASHING	Sq.M.	12.00	13.00	13.00	12.00	3.00	8.00	0.00	11
49,030	PAINTING WALLS INT. PLASTIC EMULSION	Sq.M.	44.00	46.00	48.00	48.00	18.00	22.00	0.00	40
27,020	PAINTING WALLS DISTEMPER	Sq.M.	42.00	44.00	46.00	46.00	10.00	28.00	0.00	38
28,040	PAINTING CEILINGS AND SLABS CEMENT PAINT	Sq.M.	32.00	33.00	35.00	35.00	11.00	18.00	0.00	29

WorkID	WorkName	Unit	Rate 1	Rate 2	Rate 3	Market	Material	Labour	Machine	Cos
25,010	PAINTING WOOD ENAMEL	Sq.M.	59.00	62.00	65.00	65.00	24.00	30.00	0.00	54
25,020	PAINTING WOOD VARNISH	Sq.M.	41.00	43.00	44.00	44.00	9.00	28.00	0.00	37
25,030	PAINTING WOOD POLISH	Sq.M.	25.00	26.00	28.00	28.00	5.00	18.00	0.00	23
25,510	PAINTING METAL ENAMEL	Sq.M.	58.00	61.00	64.00	64.00	23.00	30.00	0.00	53
26,010	PAINTING BASEMENT PLASTIC EMULSION	Sq.M.	44.00	46.00	48.00	48.00	18.00	22.00	0.00	40
26,020	PAINTING BASEMENT WHITE CEMENT	Sq.M.	16.00	17.00	18.00	31.00	5.00	10.00	0.00	15
27,010	PAINTING WALLS WHITE WASHING	Sq.M.	11.00	12.00	12.00	11.00	2.00	8.00	0.00	10
27,030	PAINTING WALLS PLASTIC EMULSION	Sq.M.	44.00	46.00	48.00	48.00	18.00	22.00	0.00	40
27,040	PAINTING WALLS WHITE CEMENT	Sq.M.	29.00	30.00	31.00	31.00	8.00	18.00	0.00	26
27,050	PAINTING WALLS CEMENT PAINT	Sq.M.	32.00	33.00	35.00	35.00	11.00	18.00	0.00	29
27,060	PAINTING WALLS COLOUR WASHING	Sq.M.	12.00	13.00	13.00	12.00	3.00	8.00	0.00	11
28,000	PAINTING CEILINGS AND SLABS WHITE WASHING	Sq.M.	11.00	12.00	12.00	11.00	2.00	8.00	0.00	10
29,050	PAINTING ROOFTOPS CEMENT PAINT	Sq.M.	32.00	33.00	35.00	35.00	11.00	18.00	0.00	29
28,010	PAINTING CEILINGS AND SLABS DITEMPER	Sq.M.	42.00	44.00	46.00	46.00	10.00	28.00	0.00	38
28,020	PAINTING CEILINGS AND SLABS PLASTIC EMULSION	Sq.M.	44.00	46.00	48.00	48.00	18.00	22.00	0.00	40
28,030	PAINTING CEILINGS AND SLABS WHITE CEMENT	Sq.M.	20.00	21.00	22.00	31.00	8.00	10.00	0.00	18
26,030	PAINTING BASEMENT CEMENT PAINT	Sq.M.	32.00	33.00	35.00	35.00	11.00	18.00	0.00	29

WorkID	WorkName	Unit	Rate 1	Rate 2	Rate 3	Market	Material	Labour	Machine	Cos
<b>ELECTRIFICATION AND TELEPHONE</b>										
<b>ELECTRICAL</b>										
32,102	EL MAIN SWITCH	Nos	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
32,104	EL DISTRIBUTION BOX	Nos	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
32,108	EL CEILING FAN	Nos	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
32,000	ELECTRIFICATION	L.S.	10,000.00	0.00	0.00	0.00	0.00	0.00	0.00	0
31,000	ELECTRIFICATION WISE	Points	250.00	0.00	0.00	0.00	0.00	0.00	0.00	0
32,106	EL EARTHING	Nos	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
<b>SUBSTATION</b>										
32,201	UNITISED SUBSTATION	Nos	550,000.00	575,000.00	600,000.00	500,000.00	500,000.00	0.00	0.00	500,000
<b>PANEL BOARDS</b>										
32,206	MAIN M. V. PANEL	Set	79,200.00	82,800.00	86,400.00	72,000.00	72,000.00	0.00	0.00	72,000
32,207	METERING PANEL	Nos	52,250.00	54,625.00	57,000.00	47,500.00	47,500.00	0.00	0.00	47,500
32,208	GENERATOR PANEL	Nos	29,150.00	30,475.00	31,800.00	26,500.00	26,500.00	0.00	0.00	26,500
32,209	COMMON PANEL	Nos	30,250.00	31,625.00	33,000.00	27,500.00	27,500.00	0.00	0.00	27,500
32,210	LIFT PANEL	Nos	15,950.00	16,675.00	17,400.00	14,500.00	14,500.00	0.00	0.00	14,500
<b>CABLE TERMINATION</b>										
32,212	CABLE TERMINATION LT	Nos	798.00	834.00	870.00	725.00	725.00	0.00	0.00	725
32,211	CABLE TERMINATION HT	Nos	13,750.00	14,375.00	15,000.00	12,500.00	12,500.00	0.00	0.00	12,500
<b>POWER PLUGS</b>										
32,213	POWER PLUGS 16 A	m	61.00	63.00	66.00	55.00	55.00	0.00	0.00	55
32,214	POWER PLUGS 20 A	m	82.00	86.00	90.00	75.00	75.00	0.00	0.00	75
<b>DB MAINS</b>										
32,215	DB MAINS WIRING	m	248.00	259.00	270.00	225.00	225.00	0.00	0.00	225
<b>TELEPHONE AND TV POINTS</b>										
32,216	TELEPHONE CABLE	m	38.00	40.00	42.00	35.00	0.00	35.00	0.00	35
32,217	TV ANTENA CABLE	m	35.00	37.00	38.00	32.00	32.00	0.00	0.00	32
<b>MCB DISTRIBUTION BOARDS</b>										
32,218	MCB DISTRIBUTION BOARD 4 WAY SPN	Nos	4,125.00	4,312.00	4,500.00	3,750.00	3,750.00	0.00	0.00	3,750
32,219	MCB DISTRIBUTION BOARD 4 WAY TPN	Nos	7,150.00	7,475.00	7,800.00	6,500.00	6,500.00	0.00	0.00	6,500

WorkID	WorkName	Unit	Rate 1	Rate 2	Rate 3	Market	Material	Labour	Machine	Cos
<b>LIGHT FIXTURES</b>										
32,220	TUBE LIGHT	Nos	495.00	518.00	540.00	450.00	450.00	0.00	0.00	450
32,221	WALL BRACKET LIGHT	Nos	275.00	288.00	300.00	250.00	250.00	0.00	0.00	250
32,222	CEILING LIGHT	Nos	220.00	230.00	240.00	200.00	200.00	0.00	0.00	200
<b>EARTHING</b>										
32,226	EARTHING CONDUCTOR COPPER WIRE	m	72.00	75.00	78.00	65.00	65.00	0.00	0.00	65
32,227	LIGHTNING TEST TERMINAL BOX	Nos	385.00	402.00	420.00	350.00	350.00	0.00	0.00	350
32,224	EARTH STATION G. I. PIPE	Nos	2,750.00	2,875.00	3,000.00	2,500.00	2,500.00	0.00	0.00	2,500
32,223	EARTH STATION C. I. PLATE	Nos	6,875.00	7,187.00	7,500.00	6,250.00	6,250.00	0.00	0.00	6,250
32,225	EARTHING CONDUCTOR COPPER FLAT	m	193.00	201.00	210.00	175.00	175.00	0.00	0.00	175
<b>LIGHTNING PROTECTION</b>										
32,228	LIGHTNING CONDUCTORS AL. FLAT	m	61.00	63.00	66.00	55.00	55.00	0.00	0.00	55
32,229	LIGHTNING CONDUCTORS CU. FLAT	m	324.00	339.00	354.00	295.00	295.00	0.00	0.00	295
<b>DEPOSIT TO KSEB</b>										
32,230	DEPOSITS TO KSEB	L.S.	330,000.00	345,000.00	360,000.00	300,000.00	300,000.00	0.00	0.00	300,000
<b>PLUMBING WORKS</b>										
<b>PLUMBING</b>										
34,116	PL WASH BASIN	Nos	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
34,152	PL PVC RAIN WATER PIPES	m	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
34,150	PL AC RAIN WATER PIPES	m	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
34,142	PL GS 150 MM DIA PIPE	Nos	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
34,140	PL GS 100 MM DIA PIPE	Nos	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
34,136	PL GI 12 MM DIA PIPE	m	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
34,134	PL GI 20 MM DIA PIPE	m	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
34,132	PL GI 25 MM DIA PIPE	m	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
34,130	PL GI 50 MM DIA PIPE	m	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
34,124	PL PVC 110MM DIA PIPE	m	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
34,120	PL PVC 20MM DIA PIPE	m	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
34,114	PL CLOSET ORISSA PAN	Nos	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0

WorkID	WorkName	Unit	Rate 1	Rate 2	Rate 3	Market	Material	Labour	Machine	Cos
34,112	PL CLOSET EUROPEAN	Nos	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
34,110	PL CLOSET INDIAN	Nos	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
34,101	PLUMBING L.S.	L.S.	10,000.00	0.00	0.00	0.00	0.00	0.00	0.00	0
33,000	PLUMBING POINT WISE	Points	500.00	0.00	0.00	0.00	0.00	0.00	0.00	0
34,122	PL PVC 50MM DIA PIPE	m	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
<b>GENERATOR SYSTEM</b>										
<b>GENERATOR</b>										
32,203	GENERATOR EXHAUST PIPE LINE	Set	19,250.00	20,125.00	21,000.00	17,500.00	17,500.00	0.00	0.00	17,500
32,204	GENERATOR FUEL LINE	Set	2,750.00	2,875.00	3,000.00	2,500.00	2,500.00	0.00	0.00	2,500
32,205	GENERATOR ACOUSTIC ARRANGEMENTS	Set	82,500.00	86,250.00	90,000.00	75,000.00	75,000.00	0.00	0.00	75,000
32,202	DIESEL GENSET	Nos	324,500.00	339,250.00	354,000.00	300,000.00	295,000.00	0.00	0.00	295,000
<b>OTHERS</b>										
<b>ROOFING</b>										
40,020	PAINTING PURLINES 100 75 6	Sq.M.	11.00	12.00	12.00	0.00	0.00	10.00	0.00	10
42,020	RIDGE GI	m	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
42,010	RIDGE AC	m	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
41,020	ROOFING CGI SHEETS 24	Sq.M.	231.00	241.00	252.00	0.00	210.00	0.00	0.00	210
41,010	ROOFING AC SHEETS 6MM	Sq.M.	189.00	198.00	206.00	206.00	172.00	0.00	0.00	172
40,040	PAINTING ROOFING CGI SHEETS 24 BY WEIGHT	Sq.M.	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
40,031	PAINTING WIND TIES 32 6	Sq.M.	11.00	12.00	12.00	0.00	0.00	10.00	0.00	10
40,021	PAINTING PURLINES 125 75 8	Sq.M.	11.00	12.00	12.00	0.00	0.00	10.00	0.00	10
40,011	PAINTING TRUSS 12M SPAN 3.5M SPACING	Sq.M.	11.00	12.00	12.00	0.00	0.00	10.00	0.00	10
40,010	PAINTING TRUSS 11M SPAN 3.7M SPACING	Sq.M.	11.00	12.00	12.00	0.00	0.00	10.00	0.00	10
39,040	ROOFING CGI SHEETS 24 BY WEIGHT	Kg	33.00	34.00	36.00	30.00	30.00	0.00	0.00	30
39,031	WIND TIES 32 6	Kg	23.00	24.00	25.00	0.00	21.00	0.00	0.00	21
39,030	WIND TIES 40 6	Kg	23.00	24.00	25.00	0.00	21.00	0.00	0.00	21
39,021	PURLINES 125 75 8	Kg	23.00	24.00	25.00	0.00	21.00	0.00	0.00	21
39,020	PURLINES 100 75 6	Kg	23.00	24.00	25.00	0.00	21.00	0.00	0.00	21



WorkID	WorkName	Unit	Rate 1	Rate 2	Rate 3	Market	Material	Labour	Machine	Cos
39,011	TRUSS 12M SPAN 3.5M SPACING	Kg	23.00	24.00	25.00	0.00	21.00	0.00	0.00	21
39,010	TRUSS 11M SPAN 3.7M SPACING	Kg	23.00	24.00	25.00	0.00	21.00	0.00	0.00	21
40,030	PAINTING WIND TIES 40 6	Sq.M.	11.00	12.00	12.00	0.00	0.00	10.00	0.00	10
<b>MISCELLANEOUS</b>										
60,040	GRILLS AND RAILS CONCRETE	Nos	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
18,040	TILING ROOF TOP	Sq.M.	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
60,010	GRILLS AND RAILS CAST IRON	m	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
60,020	GRILLS AND RAILS ALUMINIUM	m	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0
60,030	GRILLS AND RAILS GI PIPES	m	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0